## INTEGRATED CIRCUITS

# DATA SHEET

## 74ABT623

Octal transceiver with dual enable, non-inverting; (3-State)

Product specification Supersedes data of 1996 Sep 25 IC23 Data Handbook





Philips Semiconductors Product specification

## Octal transceiver with dual enable, non-inverting (3-State)

74ABT623

### **FEATURES**

- Octal bidirectional bus interface
- 3-State buffers
- Power-up 3-State
- Output capability: +64mA/-32mA
- Latch-up protection exceeds 500mA per Jedec Std 17
- ESD protection exceeds 2000 V per MIL STD 883 Method 3015 and 200 V per Machine Model
- Inputs are disabled during 3-State mode

### **DESCRIPTION**

The 74ABT623 high-performance BiCMOS device combines low static and dynamic power dissipation with high speed and high output drive.

The 74ABT623 device is an octal transceiver featuring non–inverting 3-State bus compatible outputs in both send and receive directions. The 74ABT623 is designed for asynchronous two-way communication between data buses. The control function implementation allows for maximum flexibility in timing. This device allows data transmission from the A bus to the B bus or from the B bus to the A bus, depending upon the logic levels at the Enable inputs (OEBA and OEAB). The Enable inputs can be used to disable the device so that the buses are effectively isolated.


## **QUICK REFERENCE DATA**

SYMBOL	PARAMETER	CONDITIONS T <sub>amb</sub> = 25°C; GND = 0V	TYPICAL	UNIT
t <sub>PLH</sub> t <sub>PHL</sub>	Propagation delay An to Bn or Bn to An	$C_L = 50pF; V_{CC} = 5V$	2.6 2.7	ns
C <sub>IN</sub>	Input capacitance OEAB, OEBA	$V_I = 0V$ or $V_{CC}$	4	pF
C <sub>I/O</sub>	I/O capacitance	Outputs disabled; $V_O = 0V$ or $V_{CC}$	7	pF
I <sub>CCZ</sub>	Total supply current	Outputs disabled; V <sub>CC</sub> =5.5V	50	μΑ

## ORDERING INFORMATION

PACKAGES	TEMPERATURE RANGE	OUTSIDE NORTH AMERICA	NORTH AMERICA	DWG NUMBER
20-Pin Plastic DIP	-40°C to +85°C	74ABT623 N	74ABT623 N	SOT146-1
20-Pin plastic SO	-40°C to +85°C	74ABT623 D	74ABT623 D	SOT163-1
20-Pin Plastic SSOP Type II	-40°C to +85°C	74ABT623 DB	74ABT623 DB	SOT339-1
20-Pin Plastic TSSOP Type I	-40°C to +85°C	74ABT623 PW	74ABT623PW DH	SOT360-1

## **PIN CONFIGURATION**



## **PIN DESCRIPTION**


PIN NUMBER	SYMBOL	NAME AND FUNCTION
1	OEAB	Output enable input, A side to B side (active-High)
2, 3, 4, 5, 6, 7, 8, 9	A0 – A7	Data inputs/outputs (A side)
18, 17, 16, 15, 14, 13, 12, 11	B0 – B7	Data inputs/outputs (B side)
19	OEBA	Output enable input, B side to A side (active-Low)
10	GND	Ground (0V)
20	V <sub>CC</sub>	Positive supply voltage

Philips Semiconductors Product specification


## Octal transceiver with dual enable, non-inverting (3-State)

74ABT623

### LOGIC SYMBOL



## LOGIC SYMBOL (IEEE/IEC)



## **FUNCTION TABLE**

INP	UTS	INPUTS/OUTPUTS				
OEBA	OEAB	An	Bn			
L	L	An = Bn	Inputs			
Н	Н	Inputs	Bn = An			
Н	L	Z	Z			
L	Н	An = Bn	Bn = An			

- H = High voltage level
- = Low voltage level = High impedance "off" state

## ABSOLUTE MAXIMUM RATINGS1, 2

SYMBOL	PARAMETER	CONDITIONS	RATING	UNIT
V <sub>CC</sub>	DC supply voltage		-0.5 to +7.0	V
I <sub>IK</sub>	DC input diode current	V <sub>1</sub> < 0	-18	mA
VI	DC input voltage <sup>3</sup>		-1.2 to +7.0	V
I <sub>OK</sub>	DC output diode current	V <sub>O</sub> < 0	-50	mA
V <sub>OUT</sub>	DC output voltage <sup>3</sup>	output in Off or High state	-0.5 to +5.5	V
I <sub>OUT</sub>	DC output current	output in Low state	128	mA
T <sub>stg</sub>	Storage temperature range		-65 to 150	°C

- 1. Stresses beyond those listed may cause permanent damage to the device. These are stress ratings only and functional operation of the device at these or any other conditions beyond those indicated under "recommended operating conditions" is not implied. Exposure to absolute-maximum-rated conditions for extended periods may affect device reliability.
- The performance capability of a high-performance integrated circuit in conjunction with its thermal environment can create junction temperatures which are detrimental to reliability. The maximum junction temperature of this integrated circuit should not exceed 150°C.

3. The input and output voltage ratings may be exceeded if the input and output current ratings are observed.

74ABT623

## RECOMMENDED OPERATING CONDITIONS

SYMBOL	PARAMETER	LIM	ITS	UNIT
		Min	Max	
V <sub>CC</sub>	DC supply voltage	4.5	5.5	V
VI	Input voltage	0	V <sub>CC</sub>	V
V <sub>IH</sub>	High-level input voltage	2.0		V
V <sub>IL</sub>	Low-level input voltage		0.8	V
I <sub>OH</sub>	High-level output current		-32	mA
I <sub>OL</sub>	Low-level output current		64	mA
Δt/Δν	Input transition rise or fall rate	0	10	ns/V
T <sub>amb</sub>	Operating free-air temperature range	-40	+85	°C

## DC ELECTRICAL CHARACTERISTICS

						LIMITS			
SYMBOL	PARAM	ETER	TEST CONDITIONS	Tai	<sub>mb</sub> = +25	°C	T <sub>amb</sub> =	-40°C 85°C	UNIT
				Min	Тур	Max	Min	Max	
V <sub>IK</sub>	Input clamp volt	age	V <sub>CC</sub> = 4.5V; I <sub>IK</sub> = -18mA		-0.9	-1.2		-1.2	V
			$V_{CC} = 4.5V$ ; $I_{OH} = -3mA$ ; $V_I = V_{IL}$ or $V_{IH}$	2.5	2.9		2.5		V
V <sub>OH</sub>	High-level outpo	ut voltage	$V_{CC} = 5.0V$ ; $I_{OH} = -3mA$ ; $V_I = V_{IL}$ or $V_{IH}$	3.0	3.4		3.0		V
			$V_{CC} = 4.5V$ ; $I_{OH} = -32mA$ ; $V_I = V_{IL}$ or $V_{IH}$	2.0	2.4		2.0		V
V <sub>OL</sub>	Low-level outpu	t voltage	$V_{CC} = 4.5V$ ; $I_{OL} = 64mA$ ; $V_I = V_{IL}$ or $V_{IH}$		0.42	0.55		0.55	V
l <sub>l</sub>	Input leakage	Control pins	V <sub>CC</sub> = 5.5V; V <sub>I</sub> = GND or 5.5V		±0.01	±1.0		±1.0	μΑ
	current	Data pins	$V_{CC} = 5.5V$ ; $V_I = GND \text{ or } 5.5V$		±5.0	±100		±100	μΑ
I <sub>OFF</sub>	Power-off leaka	ge current	$V_{CC} = 0.0V$ ; $V_I$ or $V_O \le 4.5V$		±5.0	±100		±100	μΑ
I <sub>PU</sub> / <sub>IPD</sub>	Power-up/down 3-State output current <sup>3</sup>		$V_{CC}$ = 2.0V; $V_O$ = 0.5V; $V_I$ = GND or $V_{CC}$ ; $V_{OE}$ = $V_{CC}$ ; $V_{OE}$ = GND		±5.0	±50		±50	μА
I <sub>IH</sub> + I <sub>OZH</sub>	3-State output I	High current	$V_{CC} = 5.5V; V_O = 2.7V; V_I = V_{IL} \text{ or } V_{IH}$		5.0	50		50	μΑ
I <sub>IL</sub> + I <sub>OZL</sub>	3-State output L	ow current	$V_{CC} = 5.5V; V_O = 0.5V; V_I = V_{IL} \text{ or } V_{IH}$		-5.0	-50		-50	μΑ
I <sub>CEX</sub>	Output High lea	kage current	$V_{CC} = 5.5V$ ; $V_O = 5.5V$ ; $V_I = GND$ or $V_{CC}$		5.0	50		50	μΑ
I <sub>O</sub>	Output current <sup>1</sup>		$V_{CC} = 5.5V; V_{O} = 2.5V$	-50	-100	-180	-50	-180	mA
I <sub>CCH</sub>			$V_{CC} = 5.5V$ ; Outputs High, $V_{I} = GND$ or $V_{CC}$		50	250		250	μΑ
I <sub>CCL</sub>	Quiescent supp	ly current	$V_{CC} = 5.5V$ ; Outputs Low, $V_I = GND$ or $V_{CC}$		24	30		30	mA
I <sub>CCZ</sub>			$V_{CC}$ = 5.5V; Outputs 3-State; $V_{I}$ = GND or $V_{CC}$		50	250		50	μА
			Outputs enabled, one data input at 3.4V, other inputs at $V_{CC}$ or GND; $V_{CC}$ = 5.5V		0.5	1.5		1.5	mA
Δl <sub>CC</sub>	Additional supp input pin <sup>2</sup>	ly current per	Outputs 3-State, one data input at 3.4V, other inputs at $V_{CC}$ or GND; $V_{CC}$ = 5.5V		50	250		250	μА
			Outputs 3-State, one enable input at 3.4V, other inputs at $V_{CC}$ or GND; $V_{CC} = 5.5V$		0.5	1.5		1.5	mA

## NOTES:

- 1. Not more than one output should be tested at a time, and the duration of the test should not exceed one second.
- 2. This is the increase in supply current for each input at 3.4V.
- 3. This parameter is valid for any  $V_{CC}$  between 0V and 2.1V with a transition time of up to 10msec. For  $V_{CC}$  = 2.1V to  $V_{CC}$  = 5V  $\pm$  10%, a transition time of up to 100 $\mu$ sec is permitted.

Philips Semiconductors Product specification

## Octal transceiver with dual enable, non-inverting (3-State)

74ABT623


### **AC CHARACTERISTICS**

GND = 0V;  $t_R$  =  $t_F$  = 2.5ns;  $C_L$  = 50pF,  $R_L$  = 500 $\Omega$ 


				LIMITS						
SYMBOL	PARAMETER	WAVEFORM	T <sub>2</sub>	<sub>amb</sub> = +25° 'CC = +5.0'	C V	T <sub>amb</sub> = -40° V <sub>CC</sub> = +5.	UNIT			
			Min	Тур	Max	Min	Max			
t <sub>PLH</sub> t <sub>PHL</sub>	Propagation delay An to Bn or Bn to An	1	1.0 1.0	2.6 2.7	4.1 4.2	1.0 1.0	4.6 4.6	ns		
t <sub>PZH</sub> t <sub>PZL</sub>	Output enable time to High and Low level	2	1.7 1.7	3.4 4.8	6.5 6.5	1.7 1.7	7.5 7.5	ns		
t <sub>PHZ</sub>	Output disable time to High and Low level	2	1.7 1.7	3.6 3.1	6.5 6.5	1.7 1.7	7.5 7.5	ns		

## **AC WAVEFORMS**

 $V_M = 1.5V$ ,  $V_{IN} = GND$  to 3.0V




Waveform 1. Waveforms Showing the Input to Output Propagation Delays



Waveform 2. Waveforms Showing the 3-State Output Enable and Disable Times


## **TEST CIRCUIT AND WAVEFORMS**



74ABT623

## DIP20: plastic dual in-line package; 20 leads (300 mil)

SOT146-1



## DIMENSIONS (inch dimensions are derived from the original mm dimensions)

UNIT	A max.	A <sub>1</sub> min.	A <sub>2</sub> max.	b	b <sub>1</sub>	С	D <sup>(1)</sup>	E <sup>(1)</sup>	е	e <sub>1</sub>	L	ME	Мн	w	Z <sup>(1)</sup> max.
mm	4.2	0.51	3.2	1.73 1.30	0.53 0.38	0.36 0.23	26.92 26.54	6.40 6.22	2.54	7.62	3.60 3.05	8.25 7.80	10.0 8.3	0.254	2.0
inches	0.17	0.020	0.13	0.068 0.051	0.021 0.015	0.014 0.009	1.060 1.045	0.25 0.24	0.10	0.30	0.14 0.12	0.32 0.31	0.39 0.33	0.01	0.078

### Note


1. Plastic or metal protrusions of 0.25 mm maximum per side are not included.

OUTLINE		REFER	RENCES	EUROPEAN	ISSUE DATE	
VERSION	IEC	JEDEC	EIAJ	PROJECTION		
SOT146-1			SC603		<del>-92-11-17-</del> 95-05-24	

74ABT623

## SO20: plastic small outline package; 20 leads; body width 7.5 mm

SOT163-1



### DIMENSIONS (inch dimensions are derived from the original mm dimensions)

UNIT	A max.	A <sub>1</sub>	A <sub>2</sub>	A <sub>3</sub>	bp	O	D <sup>(1)</sup>	E <sup>(1)</sup>	е	HE	L	Lp	Q	٧	w	у	z <sup>(1)</sup>	θ
mm	2.65	0.30 0.10	2.45 2.25	0.25	0.49 0.36	0.32 0.23	13.0 12.6	7.6 7.4	1.27	10.65 10.00	1.4	1.1 0.4	1.1 1.0	0.25	0.25	0.1	0.9 0.4	8°
inches	0.10	0.012 0.004	0.096 0.089	0.01	0.019 0.014	0.013 0.009	0.51 0.49	0.30 0.29	0.050	0.42 0.39	0.055	0.043 0.016	0.043 0.039	0.01	0.01	0.004	0.035 0.016	o°

### Note


1. Plastic or metal protrusions of 0.15 mm maximum per side are not included.

OUTLINE			EUROPEAN	ISSUE DATE			
VERSION	IEC JEDEC EIAJ				PROJECTION	1990E DATE	
SOT163-1	075E04	MS-013AC				<del>-92-11-17</del> 95-01-24	

74ABT623

## SSOP20: plastic shrink small outline package; 20 leads; body width 5.3 mm

SOT339-1



## DIMENSIONS (mm are the original dimensions)

						-,												
UNIT	A max.	Α1	A <sub>2</sub>	<b>A</b> <sub>3</sub>	bp	С	D <sup>(1)</sup>	E <sup>(1)</sup>	е	HE	L	Lp	Q	v	w	у	Z <sup>(1)</sup>	θ
mm	2.0	0.21 0.05	1.80 1.65	0.25	0.38 0.25	0.20 0.09	7.4 7.0	5.4 5.2	0.65	7.9 7.6	1.25	1.03 0.63	0.9 0.7	0.2	0.13	0.1	0.9 0.5	8° 0°

### Note


1. Plastic or metal protrusions of 0.20 mm maximum per side are not included.


OUTLINE		REFER	RENCES	EUROPEAN	ISSUE DATE
VERSION	IEC	JEDEC	EIAJ	PROJECTION	ISSUE DATE
SOT339-1		MO-150AE			<del>93-09-08</del> 95-02-04

74ABT623

TSSOP20: plastic thin shrink small outline package; 20 leads; body width 4.4 mm

SOT360-1





## DIMENSIONS (mm are the original dimensions)

UNIT	A max.	Α1	A <sub>2</sub>	А3	рb	С	D <sup>(1)</sup>	E <sup>(2)</sup>	е	HE	L	Lp	Œ	v	w	у	Z <sup>(1)</sup>	θ
mm	1.10	0.15 0.05	0.95 0.80	0.25	0.30 0.19	0.2 0.1	6.6 6.4	4.5 4.3	0.65	6.6 6.2	1.0	0.75 0.50	0.4 0.3	0.2	0.13	0.1	0.5 0.2	8° 0°

### Notes

- 1. Plastic or metal protrusions of 0.15 mm maximum per side are not included.
- 2. Plastic interlead protrusions of 0.25 mm maximum per side are not included.

OUTLINE		REFER	RENCES	EUROPEAN	ISSUE DATE
VERSION	IEC	JEDEC	EIAJ	PROJECTION	ISSUEDATE
SOT360-1		MO-153AC			<del>-93-06-16-</del> 95-02-04

Philips Semiconductors Product specification

## Octal transceiver with dual enable, non-inverting (3-State)

74ABT623

### Data sheet status

Data sheet status	Product status	Definition [1]
Objective specification	Development	This data sheet contains the design target or goal specifications for product development. Specification may change in any manner without notice.
Preliminary specification	Qualification	This data sheet contains preliminary data, and supplementary data will be published at a later date. Philips Semiconductors reserves the right to make chages at any time without notice in order to improve design and supply the best possible product.
Product specification	Production	This data sheet contains final specifications. Philips Semiconductors reserves the right to make changes at any time without notice in order to improve design and supply the best possible product.

<sup>[1]</sup> Please consult the most recently issued datasheet before initiating or completing a design.

### **Definitions**

**Short-form specification** — The data in a short-form specification is extracted from a full data sheet with the same type number and title. For detailed information see the relevant data sheet or data handbook.

Limiting values definition — Limiting values given are in accordance with the Absolute Maximum Rating System (IEC 134). Stress above one or more of the limiting values may cause permanent damage to the device. These are stress ratings only and operation of the device at these or at any other conditions above those given in the Characteristics sections of the specification is not implied. Exposure to limiting values for extended periods may affect device reliability.

**Application information** — Applications that are described herein for any of these products are for illustrative purposes only. Philips Semiconductors make no representation or warranty that such applications will be suitable for the specified use without further testing or modification.

### **Disclaimers**

**Life support** — These products are not designed for use in life support appliances, devices or systems where malfunction of these products can reasonably be expected to result in personal injury. Philips Semiconductors customers using or selling these products for use in such applications do so at their own risk and agree to fully indemnify Philips Semiconductors for any damages resulting from such application.

Right to make changes — Philips Semiconductors reserves the right to make changes, without notice, in the products, including circuits, standard cells, and/or software, described or contained herein in order to improve design and/or performance. Philips Semiconductors assumes no responsibility or liability for the use of any of these products, conveys no license or title under any patent, copyright, or mask work right to these products, and makes no representations or warranties that these products are free from patent, copyright, or mask work right infringement, unless otherwise specified.

Philips Semiconductors 811 East Arques Avenue P.O. Box 3409 Sunnyvale, California 94088–3409 Telephone 800-234-7381 © Copyright Philips Electronics North America Corporation 1998 All rights reserved. Printed in U.S.A.

print code Date of release: 05-96

Document order number: 9397-750-03472

Let's make things better.

Philips Semiconductors



